

CABLURI INOX AISI 316

UNI EN 10088

Ø Cablu mm	CONSTRUCTIE	MASA		
		g/m	kg	kN
1	(1+6+12) = 19 filii	6,5	80	0,78
1,5		12	200	1,97
2		19,5	330	3,24
2,5		31	515	5,05
3		45	740	7,26
4		83	1.320	12,95
5		125	2.060	20,20
6		180	2.960	29,03
7		244	4.120	40,40
8		320	5.200	51,01
10		495	7.950	77,99
12		715	11.400	111,83
14		975	14.400	141,64
16	1.270	18.800	184,43	
1	(1+6) x 7 = 49 filii	4	80	0,79
1,5		9	160	1,57
2		16	250	2,45
2,5		26	350	3,44
3		36	530	5,20
4		58	1.020	10,00
5		100	1.550	15,20
6		145	2.175	21,33
8		255	4.050	39,73
10		425	5.630	45,42
12		590	8.000	78,48
2,5		(1+6+12) x 7 = 133 filii	25	420
3	35		550	5,39
4	63		940	9,22
5	91		1.500	14,71
6	136		2.200	21,58
8	250		3.750	36,79
10	400		5.900	57,88
12	555		8.500	83,40
14	750		10.500	103,00
16	980		14.000	137,40
14	(1+6+12+17) x 6 + 49 = 216+49	800	11.700	114,80
16		1.050	15.000	147,80

